

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-19008-00-00
Spot: SESE Sec/Twnshp/Rge: 13-31S-7W
682 feet from S Section Line, 723 feet from E Section Line
Lease Name: GOHEEN Well #: A-1
County: HARPER Total Vertical Depth: 4703 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4703		140 SX CMT
SURF	8.625	247		115 SX CMT

\$ 152.85

Well Type: SWD UIC Docket No: D11070.0 Date/Time to Plug: 05/16/2006 8:30 AM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Revd. from: SCOTT HAMPEL Company: MCCOY PETROLEUM CORPORATI Phone: (316) 636-2737

Proposed Plugging Method: Squeeze perforations with 30 sacks of cement. Perforations at 1350' and squeeze 30 sacks of cement. Perforations at 300' and circulate cement to 0'. Backside squeeze from 792' to 854'. 2-7/8" tubing cemented in hole from 3479'-0'; perforations at 3530'-3580'; and RBTD 3610'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2006 2:45 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

5/16/2006 -- Took injection rate at 2-1/2 bbls @ 500 #. Pumped 50 bbls of cotton hulls and 30 sacks of cement with 50 # of cotton hulls to squeeze perforations. Cement hit perforations and squeezed off at 2000 #. Perforated at 1350'. Injection rate at 1-1/2 bbls @ 1500 #. Pumped 12 sacks of cement and squeezed off at 500 lbs. Perforated at 300'. Loaded hole and pressured up to 500 #. Cut off head to check cement.

5/17/2006 -- Ran 1" poly to 300' inside tubing and circulated tubing and casing full. Ran 1" poly to 20' on backside of casing and filled surface pipe. 75 sacks of cement on top plug at 300'.

Common with 3% CC

Acid Services #13382

Perfs:

Top	Bot	Thru	Comments
3530	3580		

**RECEIVED
KCC DISTRICT #2
MAY 25 2006
WICHITA, KS**

RECEIVED


Remarks:

Plugged through: TBG

**JUN 05 2006
KCC WICHITA**

District: 02

Signed



(TECHNICIAN)

INVOICED
June 6, 2006
20060601754