

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00318-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 33-32S-34W
2540 feet from N Section Line, 2540 feet from E Section Line
Lease Name: HITCH G Well #: 1
County: SEWARD Total Vertical Depth: 2699 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2699	0	WITH 900 SX CMT
SURF	8.625	600		300 SX CMT

\$ 87,072

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/19/2006 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT. MUD BACK TO 1700' & PUMP 25 SX CMT. MUD TO 700' 85 SX CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2006 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:
PUMP 400# HULLS & 25 SX CMT ON BOTTOM. 1ST PLUG AT 1700' WITH 25 SX CMT. 2ND PLUG PUMP 75 SX CMT FROM 600' TO SURFACE INSIDE 5 1/2" CASING.

Perfs:

Top	Bot	Thru	Comments
2658	2684		
2608	2636		
2552	2566		
2534	2544		

RECEIVED
JUN 08 2006
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.
Plugged through: CSG

District: 01
RECEIVED
MAY 24 2006
KCC Dodge City

Signed Jim Holland PIETIT
(TECHNICIAN)

INVOICED
DATE 6-9-06
2006061770

PIET