

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
RECEIVED Rev. 6/4/84  
STATE CORPORATION COMMISSION

OCT 25 1988

OCT 25, 1988  
CONSERVATION DIVISION  
Wichita, Kansas 7/89

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER NA (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Tom Rush OPERATORS LICENSE NO. 3846

ADDRESS 9301 S. Meridian, Peck, Kansas 67120 PHONE # (316) 529-2530

LEASE (FARM) KRUG WELL NO. 9 WELL LOCATION C S/2 - S/2 COUNTY Rooks

SEC. 19 TWP. 85 RGE. 17 (E) or (W) TOTAL DEPTH 3828 PLUG BACK TD 3788

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL X DOCKET NO. D3929

SURFACE CASING SIZE 8 5/8" SET AT 1,311' CEMENTED WITH 600 SACKS

CASING SIZE 5 1/2" SET AT 3482 CEMENTED WITH 175 SACKS

PERFORATED AT 4 1/2" Liner 3388 to 3519 Cemented with 125 Sacks  
3132-3336

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plug back with sand to 3,180'

Dumped 5 sacks cement, pumped cement to surface.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? \_\_\_\_\_  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11-14-88 8 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tom Rush PHONE # (316) 529-2530

ADDRESS 9301 S. Meridian, Peck, Kansas 67120

PLUGGING CONTRACTOR Gressel Corporation LICENSE NO. 5822 6/89

ADDRESS P.O. Box 322, Haysville, Kansas 67060 PHONE # (316) 773-1247

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Tom Rush  
(Operator or Agent)

DATE: 10-24-88

4

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

NOTICE  
OCT 25 1988  
EXPIRES

October 25, 1988  
WELL PLUGGING NOTICE

Krug #9 (SWD)  
C S/2 S/2  
Sec. 19-08S-17W  
Rooks County

Tom Rush  
9301 S. Meridain  
Peck, KS 67120

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist*  
\_\_\_\_\_  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200

15-163-037 72-00-02

*File*

# SIDEY DRILLING COMPANY

BUILDING & LOAN BLDG.

P. O. BOX 387

RUSSELL, KANSAS

COMPANY SHELL OIL COMPANY  
Box 426 Wichita 1, Kansas  
FARM Krug NO. 9

SEC. 19 T. 8S R. 17W  
LOC. C S/2 S/2 SW

TOTAL DEPTH 3830 1/2  
COMM. 12-9-53 COMP. 12-22-53  
SHOT OR TREATED  
CONTRACTOR Sidey Drilling Company  
ISSUED

COUNTY Rooks

CASING  
20 10  
15 1/4 8 1/4  
12 1/4 6 1/4  
18 5 5/16

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-40	Shale
40-45	Gravel
45-525	Shale & Shells
525-610	Sand & Shale
610-845	Shale & Shells
845-1020	Sand & Shale
1020-1302	Red Bed
1302-1311	Anhydrite
1311-1344	Anhydrite
1344-1795	Shale & Shells
1795-1950	Lime & Shale
1950-2230	Broken Lime
2230-2375	Lime & Shale
2375-2495	Shale, Lime & Shells
2495-2863	Lime & Shale
2863-3040	Lime
3040-3170	Lime & Shale
3170-3215	Lime
3215-3275	Lime
3275-3475	Lime & Shale
3475-3735	Lime
3735-3829	Lime & Chirt
3829-3830 1/2	Granit

RECEIVED  
STATE CORPORATION COMMISSION

OCT 25 1988  
OCT 25, 1988  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss

I, V. D. Sidey, of the Sidey Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log on H. A. Krug Well #9.

*V. D. Sidey*  
V. D. Sidey

Subscribed and sworn to before me this 9th day of January, 1954.

My Commission Expires: September 17, 1956.

*Marguerite Bepko*  
Notary Public