

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
AUG 29 2005
KCC WICHITA
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Jones & Buck Development
Address: P.O. Box 68 Sedan, Kansas 67361
Phone: (620) 725-3636 Operator License #: 31302
Type of Well: OIL GAS see well log Docket #: August 16, 2005
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Ron Rowe Chanute District (KCC District Agent's Name)
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Redd Sandstone Depth to Top: 830' Bottom: 894' T.D. 1472
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 019-26,557-0000
Lease Name: JBD-Bruen
Well Number: JBD-1
Spot Location (QQQQ): NE - NE - SW -
2290 Feet from ☐ North / ☒ South Section Line
2990 Feet from ☒ East / ☐ West Section Line
Sec. 30 Twp. 33 S. R. 13 ☒ East ☐ West
County: Chautauqua
Date Well Completed: June 27, 2001
Plugging Commenced: August 18, 2005
Plugging Completed: August 18, 2005

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Redd Sandstone	Oil	1473'	Surface	4 1/2"	1473' 1458	None
Weiser Sandstone	Oil	40'	Surface	8 5/8"	40	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bullhead pumped 10 sacks portland cement and 8 barrels gelled water. Pressured well
to 800# and shut in. Ran 1" spool hose to 350' and pumped/circulated 35 sacks cement
to surface. Pulled spool hose and topped well off with cement. Restore location.

Name of Plugging Contractor: Elmore's Inc. License #: 32884
776 State Highway 99 South Sedan, Kansas 67361
Address: _____
Name of Party Responsible for Plugging Fees: Jones & Buck Development
Kansas Chautauqua
State of _____ County, _____, ss.
Thomas H. Oast

(Employee of Operator) or (Operator) on above-described well, being first duly
sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the
same are true and correct, so help me God.



(Signature) Tim M. Oast
(Address) P.O. Box 68 Sedan, Kansas 67361

SUBSCRIBED and SWORN TO before me this 26 day of August, 2005
Tim Doty My Commission Expires: 4-8-2006
Notary Public