

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUN 07 2006

KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Tri United, Inc.
Address: 950 270th Ave Hays, Ks 67601
Phone: (785) 628-3670 Operator License #: 03194
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4-10-06 (Date)
by: Herb Dienes (KCC District Agent's Name)
is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
topeka Depth to Top: 3255 Bottom: 3261 T.D. 3464
LKC Depth to Top: 3506 Bottom: 3754 T.D. 3754
Arb Depth to Top: 3838 Bottom: 3855 T.D. 3855

API Number: 15-051-254760000
Lease Name: Pfeifer
Well Number: 1-B
Spot Location (Quad): AP N¹/₂ NW-SW-NE
1490' Feet from North / South Section Line
2310' Feet from East / West Section Line
Sec. 36 Twp. 13 S. R. 20 East West
County: Ellis
Date Well Completed: 4-10-06
Plugging Commenced: 4-14-06
Plugging Completed: 4-14-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Top	wtr & oil	Surf	212'	8 5/8	212'	-0-
KC	wtr & Oil	Surf	3854'	5 1/2	3854'	997'
Arb	wtr & Oil					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1 yd of sand on bottom with 5 sks cement, pumped 125sk w/300# nulls after Shooting off casing at 997' Pulled casing to 825' & spot 50sk w/200# hulls. Pulled up to 160' & circulated cement to surface w/50sks. Came out w/casing capped off surface with 5 sks, Hole full. Totals sacks 230 60/40 poz 10% gel

Name of Plugging Contractor: Geist, Ron dba wildcat well service
Tri United, Inc. / Allied Cementing License #: 03194 33612
Address: 950 270th Ave Hays, Ks 67601
Name of Party Responsible for Plugging Fees: Tri United, Inc.
State of Ks County, Ellis, ss.

Eugene Leiker (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Eugene E Leiker
(Address) 950 270th ave Hays, Ks 67601

ROBERTA ANGELL
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 10-24-08
and SWORN TO before me this 7th day of June 2006
Roberta Angell My Commission Expires: 10-24-08
Notary Public

Pkt

ALLIED CEMENTING CO., INC. 25810

RECEIVED

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

JUN 07 2006 SERVICE POINT:
Russell

KCC WICHITA

DATE <u>4-14-06</u>	SEC. <u>36</u>	TWP. <u>13</u>	RANGE <u>20</u>	CALLED OUT <u>8:00 AM</u>	ON LOCATION <u>10:15 AM</u>	JOB START <u>10:30 AM</u>	JOB FINISH <u>3:30 PM</u>
LEASE <u>PFEIFER</u>		WELL # <u>1-B</u>	LOCATION <u>Hogback - 2 1/2 S. 1/2 W 1/2 S</u>	COUNTY <u>ELLIS</u>	STATE <u>KANSAS</u>		
OLD OR NEW (Circle one)							

CONTRACTOR RON GEIST "CSB" PULLERS OWNER Same
 TYPE OF JOB Plug ABANDONED well
 HOLE SIZE 7 7/8 T.D.
 CASING SIZE 5 1/2 DEPTH 3838
TUBING SIZE 8 5/8 DEPTH 220'
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG.
 PERFS. PERF T
 DISPLACEMENT

EQUIPMENT

PUMP TRUCK CEMENTER GLENN
 # 398 HELPER GARY
 BULK TRUCK
 # 396 DRIVER BRIAN
 BULK TRUCK
 # DRIVER Kyle

REMARKS:

SHOT OFF @ 997' Spot 125 SK w/300#
Hull's. Pulled up to 825 + Spot 50 SK
w/200 # Hull's. Pulled up to 160' &
CIRC Cement To SURFACE w/50 SK
CAME out w/CSG. CAP OFF w/5 SK

Hole STAYED Full

Shankie

STATE REP. KCC ON LOC.
JAY PFEIFER

CHARGE TO: Eugene Leiker "TRI-UNITED"

STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE _____

CEMENT (USED 230. SK)
 AMOUNT ORDERED 275 SK 60/40 102 GEL

500# Hull's

COMMON	<u>138</u>	@	<u>9.62</u>	<u>1324.00</u>
POZMIX	<u>92</u>	@	<u>5.20</u>	<u>478.40</u>
GEL	<u>16</u>	@	<u>15.00</u>	<u>240.00</u>
CHLORIDE		@		
ASC		@		
<u>Hull's</u>	<u>5</u>	@	<u>23.00</u>	<u>115.00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>299</u>	@	<u>1.70</u>	<u>508.30</u>
MILEAGE	<u>44 Tow Mile</u>			<u>920.92</u>
TOTAL				<u>3587.42</u>

SERVICE

DEPTH OF JOB				
PUMP TRUCK CHARGE				<u>650.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>44</u>	@	<u>5.00</u>	<u>220.00</u>
MANIFOLD		@		
		@		
		@		
TOTAL				<u>870.00</u>

PLUG & FLOAT EQUIPMENT

	@			
	@			
	@			
	@			
	@			
TOTAL				

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____