

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION RECEIVED
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
 K.A.R. 82-3-117

Form CP-4
 December 2003
 Type or Print on this Form
 Form must be Signed
 All blanks must be Filled

JUN 07 2006

KCC WICHITA

Lease Operator: JOHN O. FARMER, INC.
 Address: P.O. Box 352 Russell, KS 67665
 Phone: (785) 483-3144 Operator License #: 5135
 Type of Well: D & A Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 5/16/06 (Date)
 by: Herb Deines (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-167-23,338-00-00
 Lease Name: STECKEL "A"
 Well Number: 1
 Spot Location (QQQQ): - App - NE - NW
740 Feet from North / South Section Line
~~990~~ Feet from East / West Section Line
 Sec. 17 Twp. 12 S. R. 14 East West
 County: Russell
 Date Well Completed: 5/17/06
 Plugging Commenced: 3:30AM 5/17/06
 Plugging Completed: 5:45AM 5/17/06

*KCC PET
 6/8/06
 per
 C-1*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		418'	Surface	8 5/8"	408'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 875'W/25sk 15sk In Rat Hole Circulated 1st Plug 15 Minutes W/55 Vis Mud
 2nd Plug @ 475'W/60sk 10sk In Mouse Hole Plugs displaced with mud
 3rd Plug @ 40'W/10sk Total 120sk 60/40Poz 6%Gel W/1/4#CF/sk By Allied Cementing
 Completed @ 5:45AM 5/17/06


Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548
 Address: P.O. Box 763 Hays, KS 67601
 Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.
 State of Kansas County, Russell, ss.

John O. Farmer III (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John O. Farmer III
 (Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 6th day of June, 20 06

Margaret A. Schulte
 Notary Public My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PET