

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUN 05 2006

KCC WICHITA

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Popp Operating, Inc.

Address: PO Box 187 Hoisington, KS 67544

Phone: (620) 786-5515 Operator License #: 32325

Type of Well: OIL Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3/28/06 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 4183' Bottom: 4193' T.D. 4297'

Viola Depth to Top: 4270' Bottom: 4276' T.D. 4297'

Depth to Top: Bottom: T.D.

API Number: 15 - 145-20471-00-00

Lease Name: Wurm "B"

Well Number: 1

Spot Location (QQQQ): NE - NE - SE - Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 32 Twp. 23 S. R. 16 East West

County: Pawnee

Date Well Completed: 6/23/77

Plugging Commenced: 3/28/06

Plugging Completed: 3/31/06

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes data for 8-5/8" and 4-1/2" casings.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Sand @ 4130', baled 4 sx cement, ripped @ 2610', parted @ 580'. Pulled 580' csg, ran tbg to 1060', pumped 30sx cement, pulled tbg to 600', pumped 12 sx gel & 50 sx cement, pulled tbg to 300', pumped 60 sx cement, pulled tbg to 40', pumped 15 sx cement.

Name of Plugging Contractor: Quality Well Svc, Inc. License #: 31925

Address: 401 West Main Lyons KS 67554

Name of Party Responsible for Plugging Fees: Popp Operating, Inc.

State of Kansas County, Barton, ss.

Rickey Popp (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Rickey Popp

(Address) PO Box 187 Hoisington, KS 67544

SUBSCRIBED and SWORN TO before me this 2nd day of June, 2006

Notary Public Jane M. Steiner My Commission Expires: 5/20/07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



KCC PRT 018106 Per CP2/3

PRT

ALLIED CEMENTING CO., INC. 23659

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
GREAT BEND

RECEIVED
JUN 05 2006
KCC WICHITA

DATE <u>03-31-06</u>	SEC. <u>32</u>	TWP. <u>23s</u>	RANGE <u>16W</u>	CALLED OUT <u>9:00 AM</u>	ON LOCATION <u>10:30 AM</u>	JOB START <u>11:00 AM</u>	JOB FINISH <u>12:15 PM</u>
LEASE <u>Warm B</u>	WELL # <u>1</u>	LOCATION <u>LADDER 11 1/2 SO W/SIDE</u>			COUNTY <u>TAUWEE</u>	STATE <u>KS</u>	

OLD OR NEW (Circle one)

CONTRACTOR Quality Well Service
 TYPE OF JOB PLUG WITH STALLING
 HOLE SIZE 7 7/8" T.D. 4301
 CASING SIZE 8 1/2" DEPTH 4301
 TUBING SIZE 2 3/8" DEPTH 1060
 DRILL PIPE DEPTH _____
 TOOL DEPTH _____
 PRES. MAX 5000 MINIMUM _____
 MEAS. LINE SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER BPP Operating Inc.

CEMENT
 AMOUNT ORDERED 160 LB 60/40 6% GEL
12 LB GEL
USED ISSUED

EQUIPMENT

PUMP TRUCK CEMENTER BUD
 # 120 HELPER BUDA
 BULK TRUCK
 # 342 DRIVER DOUD
 BULK TRUCK
 # DRIVER _____

COMMON	<u>93 LB</u>	@	<u>9.60</u>	<u>892.80</u>
POZMIX	<u>62 LB</u>	@	<u>5.20</u>	<u>322.40</u>
GEL	<u>20 LB</u>	@	<u>15.00</u>	<u>300.00</u>
CHLORIDE		@		
ASC		@		
HANDLING	<u>180 LB</u>	@	<u>1.70</u>	<u>306.00</u>
MILEAGE	<u>180 LB 07</u>		<u>34</u>	<u>428.40</u>
TOTAL				<u>2,249.60</u>

REMARKS:

1st Plug 1060' Book Circ. lined 30 LB
60/40 6% GEL Displace to DAL
2nd Plug 600' MINIZAL 6% GEL Sunday
50 LB 60/40 6% GEL Displace to
DAL 3rd Plug 300 FT Mix 60 LB
60/40 6% GEL Displace to Box
4th Plug 10 FT Mix 15 LB 60/40 6% GEL
CEMENT CALCULATED

SERVICE

DEPTH OF JOB	<u>1060'</u>			
PUMP TRUCK CHARGE				<u>650.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>34</u>	@	<u>5.00</u>	<u>170.00</u>
MANIFOLD		@		
TOTAL				<u>820.00</u>

CHARGE TO: BPP Operating Inc
 STREET PO Box 187
 CITY Wilmington STATE KS ZIP 67544

PLUG & FLOAT EQUIPMENT

	@			
	@			
	@			
	@			
	@			
TOTAL				

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Jan M...

PRINTED NAME _____

Quality Well Service, Inc.

401 West Main
Lyons, KS 67554

Invoice

Date	Invoice #
4/6/2006	753

Bill To
Popp Operating, Inc. Box 187 Hoisington, KS 67544

RECEIVED
JUN 05 2006
KCC WICHITA

P.O. No.	Terms	Lease Name
	net	Wurm "B"

Description	Qty	Rate	Amount
Rig Time	30	155.00	4,650.00T
Trucking Floor		100.00	100.00T
Sand		35.00	35.00T
Cement	4	9.00	36.00T
Shots		150.00	150.00T
Torch		50.00	50.00T
Water Truck	6	65.00	390.00T
Backhoe	6	65.00	390.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
Fresh Water		20.00	20.00T
3-28-06 Drove to location, unhooked well head, raised pole, changed over to pull rods, moved pumping unit with backhoe, pulled rod subs, drove home.			
3-29-06 Drove to location, laid down rods, changed over for bottom, loaded hole with water, dug cellar, unpacked casing head, set floor, checked hole, sand was at 4130', bailed 4 sacks cement with baler, pulled slips, cut surface off 4' below ground, had 19 inches stretch, drove home.			
3-30-06 Drove to location, ripped casing at 2610', worked pipe, pipe was on tension, casing parted at 580', screwed back on casing, pulled on casing and parted again, pulled casing out, changed over to run tubing in, drove home.			
		Subtotal	
		Sales Tax (6.3%)	
		Total	

Quality Well Service, Inc.

**401 West Main
Lyons, KS 67554**

Invoice

Date	Invoice #
4/6/2006	753

Bill To
Popp Operating, Inc. Box 187 Hoisington, KS 67544

**RECEIVED
JUN 05 2006
KCC WICHITA**

P.O. No.	Terms	Lease Name
	net	Wurm "B"

Description	Qty	Rate	Amount
3-31-06 Drove to location, ran 20 joints tubing, shut down to pump on tubing, cleared tubing, ran 2 more joints, pumped 30 sacks at 1060', pulled to 600', pumped 12 gel & 50 sacks, pulled to 300', pumped 60 sacks, pulled to 40', pumped 15 sacks, tore down floor & rig, emptied pit, cleaned up location.			
Subtotal			\$5,876.00
Sales Tax (6.3%)			\$370.19
Total			\$6,246.19