

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-62-3-117

15.205-19213-0000

API NUMBER \_\_\_\_\_  
 LEASE NAME UNIT 1 - KEYS HEIRS

WELL NUMBER OLD WELL # A  
2900' Ft. from S Section Line

2060' Ft. from E Section Line  
 SEC. 28 TWP. 30 RGE. 16 (E) or (W)

COUNTY WILSON

Date Well Completed ?

Plugging Commenced 9/21/01

Plugging Completed 11/26/02

12-20-02  
 12-20-02

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR AXEP, INC

ADDRESS P.O. Box 1176 INDEPENDENCE KS

PHONE#(620) 331-0144 OPERATORS LICENSE NO. 3830

Character of Well PRODUCER OIL KCC 6/8/06 PKT  
PERC 2/3  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/20/01 (date)  
 by MR. TONY WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? NO - OLD WELL FRACED INTO

Producing Formation NEODESHA SA Depth to Top 770' Bottom 800' T.D. 2800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>SURFACE</u>		<u>0</u>	<u>100'</u>	<u>12"</u>	<u>100' +</u>	<u>0</u>
<u>PRODUCTION</u>		<u>0</u>	<u>750'</u>	<u>5"</u>	<u>750' +</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:  
RAN 1 1/2" POLY PIPE TO 675' INSIDE 5" CASING. COULD GO NO DEEPER  
PLACED 10 SK CEMENT AND POH 1 1/2" PIPE. RAN 1 1/2" PIPE INSIDE 5" TO  
470' - TOP OF CEMENT PLUG. WASHED DOWN ANNULUS (12" - 5") TO 165' COULD  
GO NO FURTHER. CEMENTED UP INSIDE 5" AND ANNULUS. 3 SK TOTAL.

Name of Plugging Contractor AXEP, INC License No. 3830

Address P.O. Box 1176 INDEPENDENCE, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AXEP, INC -

STATE OF KANSAS COUNTY OF Montgomery, ss.

JURGEN S. HANKE (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

RECEIVED  
 KCC District #3

(Signature) Jurgen Hanke

(Address) P.O. Box 1176

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 2002

My Commission Expires: KS 2/23/05

Notary Public

DANA L. GORMAN  
 Notary Public - State of Kansas  
 My Appt. Expires 2/23/05

Form CP-1  
 Revised 05-88

pet