

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Bear Petroleum, Inc.  
Address: PO Box 438, Haysville, KS 67060  
Phone: (316) 524-1225 Operator License #: 4419  
Type of Well: SWD Docket #: D-23,895  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 3/14/06 (Date)  
by: Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-167-22,563-00-00  
Lease Name: Berry  
Well Number: 4 SWD Per CP2/3 Pkt 6-7-06  
Spot Location (QQQQ): S2 - SW - NE - NE  
4240 Feet from  North /  South Section Line  
990 Feet from  East /  West Section Line  
Sec. 33 Twp. 15 S. R. 13  East  West  
County: Russell  
Date Well Completed: \_\_\_\_\_  
Plugging Commenced: 5-23-06  
Plugging Completed: 5-25-06

KCC Pkt  
6-7-06  
Per  
CP2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4	468	
				7	3565	1150

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Shot casing at 1150', cut surface pipe off 4' below ground, pulled to 1020', pumped 120 sacks, 500 hulls, pulled to 450', pumped 50 sacks, 100 hulls, pulled to 150', circulated with 75 sacks.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 401 West Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc.

State of Kansas County, Sedgwick, ss.

R. A. Schremmer

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

(Address)

P.O. Box 438, Haysville, KS 67060

SUBSCRIBED and SWORN TO before me this 2nd day of June, 20 06

Shannon Howland  
Notary Public

My Commission Expires: 3/10/08

SHANNON HOWLAND  
Notary Public - State of Kansas  
My Appt. Expires 3/10/08

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

JUN 05 2006

KCC WICHITA

Pkt

# Quality Well Service, Inc.

401 West Main  
Lyons, KS 67554

# Invoice

Date	Invoice #
05/30/2006	768

Bill To
Bear Petroleum, Inc. PO Box 438 Haysville KS 67060

P.O. No.	Terms	Lease Name
	net	Berry 4 SWD

Description	Qty	Rate	Amount
Rig Time	12.5	160.00	2,000.00T
Torch		50.00	50.00T
Trucking Floor		100.00	100.00T
Water Truck	4	65.00	260.00T
Backhoe	1.5	65.00	97.50T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
Fresh Water		20.00	20.00T
5-23-06 Drove to location, Raised pole, drove home.			
5-25-06 Drove to location, dug cellar, unpacked casing head, set floor, pulled slips, had 9" stretch, shot casing at 1150', came free, cut surface pipe off 4" below ground, pulled casing to 1020', pumped 120 sacks and 500# hulls, pulled to 450', pumped 50 sacks and 100# hulls, pulled to 150', circulated with 75 sacks, pulled rest of pipe, tore down floor & rig, emptied pit.			

RECEIVED  
JUN 05 2006  
KCC WICHITA

<b>Subtotal</b>	\$2,582.50
<b>Sales Tax (7.3%)</b>	\$188.52
<b>Total</b>	\$2,771.02

