

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

JUN 05 2006

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

KCC WICHITA

Lease Operator: Intermountain Refining Co., Inc.

Address: PO Box 35, Farmington, NM 87499

Phone: (505) 326-2668 Operator License #: 32356

Type of Well: Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: April 5, 2006 (Date)

by: Jerry Stapleton, Dist #1 Dodge City (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Chase Depth to Top: 2765 Bottom: 2773 T.D. 2840

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-171200510000

Lease Name: JM Hammeke JM

Well Number: #1

Spot Location (QQQQ): C - NW -

1320 Feet from North / South Section Line

1320 Feet from East / West Section Line

Sec. 34 Twp. 18 S. R. 31 East West

County: Scott

Date Well Completed: 07/22/1973

Plugging Commenced: 05/10/2006

Plugging Completed: 05/10/2006

KCC Pkt 6-6-06 per CP 2/3

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Chase group with Gas content.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Set CIBP at 1650'. Perforate at 1620'. Mix 400 sacks 60-40 w/6% gel cement. Pump cement at 1200-1000psi down 5 1/2"

production casing, end with 200# hulls, total cement 220 sacks. Close off 5 1/2" casing. Pump cement down 8 5/8" surface

casing at 200 psi, total cement 180 sacks to surface. Cut off and remove casing approximately 4' below ground.

KCC representative was present on site during plugging operations.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382

Address: N Hwy 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: Intermountain Refining Co., Inc.

State of New Mexico County, San Juan, ss.

Rick L. Hurt Secretary/Treasurer

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) 1921 Bloomfield Blvd, Farmington, NM 87401

SUBSCRIBED and SWORN TO before me this 31 day of May, 2006

[Handwritten Signature of Notary Public]

Notary Public

My Commission Expires: Nov 6, 2008

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Pkt