

RECEIVED

FEB 27 2006

KCC WICHITA

Form CP-4
December 2003Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

15-125-01263-00-00

Lease Operator: COLT ENERGY, INCAddress: P O BOX 388, IOLA, KS 66749Phone: (620) 365-3111 Operator License #: 5150Type of Well: OLD WELL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)The plugging proposal was approved on: 2-9-06 (Date)by: ALAN DUNNING (KCC District Agent's Name)Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

INFO UNKNOWN Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-OLD WELLLease Name: HILLIEWell Number: 1

Spot Location (QQQQ): _____ - NW - SW - NW

3659 Feet from ☐ North / ☒ South Section Line155 Feet from ☐ East / ☒ West Section LineSec. 34 Twp. 31 S. R. 17 ☒ East ☐ WestCounty: LABETTE MONTGOMERY KCC WHMDate Well Completed: UNKNOWNPlugging Commenced: 2-9-06Plugging Completed: 2-13-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
UNKNOWN	-----			10"	APPROX 20'	NONE
				6 1/4	740.80'	NONE


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RAN 2" TO 618' WASHED 2" ON DOWN TO 740.80' WASHED 1" DOWN ON OUTSIDE OF 6 1/4 TO 200'. CONSOLIDATED PUMPED
120SXS CEMENT INSIDE 6 1/4 TO SURFACE AND PUMPED 80SXS ON OUTSIDE OF 6 1/4 FROM
200' TO SURFACE PULLED PIPE OUT WELL PLUGGED.

Name of Plugging Contractor: CONSOLIDATED OIL WELL SERVICESLicense #: 31440Address: P O BOX 884, CHANUTE, KS 66720Name of Party Responsible for Plugging Fees: COLT ENERGY, INCState of KANSAS County, ALLEN, ss.EMPLOYEE OF OPERATOR

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Donnis Hershner(Address) P O BOX 388, IOLA, KS 66749SUBSCRIBED and SWORN TO before me this 23rd day of February, 2006Shirley A. Stotler
Notary PublicMy Commission Expires: 2-10-2008

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PPT

FEB 21 1964

KCC WICHITA

620-431-9210 OR 800-467-8676

TICKET NUMBER 08311

LOCATION Eureka

FOREMAN Troy Strickler

TREATMENT REPORT & FIELD TICKET

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
2-13-06	1828	Hillie #1				MC
CUSTOMER						
Colt Energy, Inc.						
MAILING ADDRESS						
P.O. Box 388						
CITY	STATE	ZIP CODE	TRUCK #	DRIVER	TRUCK #	DRIVER
Tola	Ks.		463	Alan		
			442	Rick P.		

JOB TYPE <u>Plug Job</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT _____
CASING DEPTH <u>740'</u>	DRILL PIPE _____	TUBING _____	OTHER <u>200' x 10'</u>
SLURRY WEIGHT <u>14"</u>	SLURRY VOL _____	WATER gal/sk <u>7.0</u>	CEMENT LEFT in CASING <u>740'</u>
DISPLACEMENT _____	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____
REMARKS: <u>Safety Meeting: Rig up to 2 3/8" Tubing. Cement 740' to surface</u> <u>w/ 120sks 60/40 Poz-mix Cement. 4% Gel, 1% CaCl₂ @ 14" Refgal.</u> <u>Rig up to 1" Set in between 6 1/4" Casing + 10" Casing. Cement 200' to Surface</u> <u>With 80sks 60/40 Poz-mix 4% Gel, 1% CaCl₂ @ 14" Refgal. Pull'd Tubing.</u> <u>Topped hole off. Job Complete.</u>			

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	\$25.00	\$25.00
5406	40 miles	MILEAGE	3.15	126.00
1131	200 sks	60/40 Poz-mix Cement	8.40	1680.00
1118A	14 sks	Gel 4%	7.00	98.00
1102	2 sk - 172"	Cadiz 12	.64	110.08
5407A	8.6 Ton	Ton-Mileage Bulk Truck	1.05	361.20
		Thank You!		
			Sub Total	2900.28
		5.3%	SALES TAX	100.06
			ESTIMATED TOTAL	3000.34

AUTHORIZATION Called by John

TITLE

DATE _____