

11-1 4-032103 15-163-01811-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1956

S2 S2 NW /4 SEC. 05 , 08 , 17 W
2970 feet from S section line
3960 feet from E section line

Operator license# 5363 Lease: Frank Well # 2
Operator: Berexco, Inc. County: Rooks 106.63
Address: P.O. Box 723 Well total depth 3281 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 100 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cement Company License# _____

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 1 Month: November Year: 1995

Plugging proposal received from: Curtis Gabel

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order work string of tubing.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 6:00 P.M., Day: 1, Month: November, Year: 1995

Actual plugging report: 8 5/8" set at 100' cwc with N/A sxs. 5 1/2" set at 3278' with N/A sxs. Squeezed at 770' with 150 sxs - 905' with 150 sxs - 2470' with 150 sxs. Ran tubing to 3100'. Displaced 100 sxs cement blend with 300# hulls. Pulled tubing to 1600'. Displaced to surface with 100 sxs cement blend with 150# hulls mixed in. Pulled tubing. Tied onto 5 1/2" casing. Squeezed with 50 sxs cement blend for total of 250 sxs. to Max. P.S.I. 500#. Close in P.S.I. 200#. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 300#. Close in P.S.I. 100#. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES _____ NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES _____ NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ WICHITA, KS _____ GL

I did not observe the plugging.

Carl Goodrow
(agent)

NOV 17 1995 11-17-95

DATE 11-20-95
INV. NO. 44059