

6 070319 15-163-22597-00-00

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,597

SW-NW-NE, SEC. 7, T. 8 S, R. 17

4290 feet from N Section line

2210 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name HARBE Well # 2

Operator: TXO PRODUCTION CORP.

County ROOKS. 112.84

Name & Address 200 W. DOUGLAS, #300

Well Total Depth 3472 feet

WICHITA, KANS.

Conductor Pipe: Size 0 feet

67202

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated TAG # 607

Plugging Contractor MURFIN DRILLING INC License Number 6033

Address 200 WEST DOUGLAS, #300 WICHITA, KANS. 67202

Company to plug at: Hour: 6:00 PM Day: 29th Month: JAN Year: 1985

Plugging proposal received from ALFRED AUGUSTINE

(company name) MURFIN DRILLING INC (phone) 316-265-9441

were: 8 5/8" - 259 FT SP. CUL # 200 COMMUN CA-CL - BY DOWELL

ORDER 220 50/50 Formix GEL - CA-CL - 1 5/8" FLAME AND 8 5/8" PLUG

SPOT WITH DRILL STEM - RECONDITION HOLE (50 VIS) HEAVY MUD BETWEEN ALL PLUGS.

NO CIRCULATION PROBLEMS - ARRACHLE @ 3363 FT, ELV 1919 - ANN. 1348.

MUD. VIS - 44 - Weight 9.2 - Chlorides 2000

Plugging Proposal Received by Marion Schmidt
BOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 PM Day: 29th Month: JAN Year: 1985

ACTUAL PLUGGING REPORT ORDERED 220 50/50 Formix GEL - CA-CL - 1 5/8" FLAME & 8 5/8" PLUG

SPOTTED WITH DRILL STEM - RECONDITIONED HOLE HEAVY MUD BETWEEN ALL PLUGS

1st Plug @ 3330 # 25 5/8" cnt, 2nd Plug @ 1320 # 25 5/8" cnt

3rd Plug @ 450 # 100 5/8" cnt # 1 5/8" FLAME, 4th Plug @ 270 # 100 5/8" cnt

5th Plug @ 40 # 10 5/8" cnt, 10 5/8" PLUG (CIRCUMFERENTIAL)

CEMENTED BY DOWELL CMT.

STATE CORPORATION COMMISSION

2-11-85

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-14-85

Signed Marion Schmidt
(TECHNICIAN)

INV. NO. 6968 1-29 FEB 27 1985

FORM CP-2/3 Rev. 01-84