

4 060002

6-27

API NUMBER 15-163-21,620-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

App. W2-SW-SW SEC. 5, T 8s S, R 17w ~~(W) (E) (X)~~

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

585 feet from S section line

Operator: Grahan-Michaelis Corp.

Name & Address 211 N. Broadway

Wichita, KS 67202

4950 feet from E section line

Lease Name Bemis Well # 1-5

County Rooks 109.75

Well Total Depth 3377 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Pipe Pullers License Number 6050

Address P.O. Box 347 Chase, KS 67524

Company to plug at: Hour: 9:30AM Day: 27 Month: June Year: 19 89

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: Pull casing to 1600' after sanding back bottom of hole to 3320' and spotting 4 sxs. cement. Spot 10 sxs. gel w/3sxs. hulls and pull pipe to 1400'. Spot 50 sxs. cement w/2 sxs. hulls and 10 sxs. gel w/4 sxs. hulls. Pull to 700' and circ. Pull rest of pipe and fill hole with cement to surface.

Order 250 sxs 65/35 poz. 4%Gel w/1/4# flocel

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Yes Part None

Operations Completed: Hour: 1:45PM Day: 27 Month: June Year: 1989

ACTUAL PLUGGING REPORT Kelso Casing Pullers spotted sand to 3320 and topped w 4sxs cem. w dump bailer. Shot and recovered 2630' of 4 1/2" casing. Pulled casing to 1600' and spotted 10 sxs. gel w/3 sxs. hulls. Pulled casing to 1400' and spotted 50 sxs. cem. w/2sxs. hulls. Balanced w 10sxs. gel w/4 sxs. hulls. Pulled casing to 700' and pumped 100 sxs. cem. Didn't cir. due to to bridge uphole against casing. Pressured to 500#. Pulled casing to 350' and cir. 80 sxs. cem. Pulled casing and filled hole to surface of casing with cement.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED Observe this plugging.

DATE 7-5-89

INV. NO. 25230

Signed Herb Deines (TECHNICIAN)