

4-060482

15-163-21715-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,175

NE NE SE /4 SEC. 05, 08 S, 17 W
2310 feet from S section line
330 feet from E section line

Operator license# 5134

Lease Stamper well # 1-5

Operator: Graham-Michaelis Corporation

County Rooks

Address: P.O. Box 247
Wichita, Kansas 67201

Well total depth 3375 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 254 feet

109.69

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524-0347

Company to plug at: Hour: 10:30A.M Day: 16 Month: December Year: 93

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 210 sxs. 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

12-23-93

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1993

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 5:00P.M., Day: 16, Month: December, Year: 93

Actual plugging report: 8 5/8" to 254'. 4 1/2" to 3375'. Sand back to 3000' and spot. 4 sxs. cement with dumper bailer. Shot at 1750' and 1350'. Didn't pull free. Mixed and pumped 100 sxs. cement with 150# hulls and displaced to 950'. Shot casing at 910' and didn't pull free. Shot at 700'. Pumped 50 sxs. cement with 100# hulls. Pressure to 500#. Shut down. Pulled casing to 400'. Pumped 50 sxs. cement with 100# hulls to circulate cement at surface. Pulled casing. Filled to surface with 10 sxs. cement.

Remarks: Allied cementing.

Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO

Bottom plug(in place):YES X, CALC , NO Dakota plug:YES X, NO

Plugged through TUBING , CASING X. Elevation: 1916 GL

I did X [] did not [] observe the plugging.

Herb Deines & Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE 12-29-93

INV. NO. 39587

12-16