

6 041023

3-30
API NUMBER 15-163-27229-00-07 33 OK

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW SW, SEC. 5, T. 8 S, R. 17 W/Ex
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

RECEIVED
STATE CORPORATION COMMISSION
APR - 2 1989

Lease Name Bemis Well # 2 SWD

Operator: Rose Energy Inc.

County Rooks 113.75

Name & Address 550 E. Fourth

Well Total Depth 3500 feet

Russell, Ks. 67663

CONSERVATION DIVISION
Wichita, Kansas
4/12/89

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 760' w/cwc 425sk

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Russell, Ks.

Company to plug at: Hour: 3:30PM Day: 30 Month: Mar Year: 19 89

Plugging proposal received from David Burns

(company name) _____ (phone) _____

were: 5 1/2" casing set at 3371' w/150 sks. O.H. 3371' to 3500'. Ordered 100 sks common plus ordered 350 sks 60/40 Poz 6% Gel 3% Cal Cl w/1/4# F.C.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30PM Day: 30 Month: Mar Year: 19 89

ACTUAL PLUGGING REPORT March 15, 1989 Ran w.l.m. to 818'; ran flag found holes in casing at 771'. (base of S.P.) 760'; Pumped in 225 sks 60/40 Poz 4% Gel w/1/4# F.C. - no pressure-killed sw flow: March 30, 1989 pumped add 25 sks cement in annulus; Max 500# S.I. 500#.

March 30, 1989 ran w.l.m. to 766' - circulated/washed tubing to 956'. Pulled 1 jt. Ran tubing to 924'; Spotted 100 sks common on bottom, stuck tubing, backed off tubing at 310';

Pumped 50 sks 60/40 Poz 6% Gel plug 1/4# F.C. in cement; circ cement to surf: pulled tubing hooked up to 5 1/2" casing; squeezed in add 50 sks cement: Max 500# psi. S.I. 400# psi.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Dennis L. Hamel (TECHNICIAN)

DATE 4-20-89

INV. NO. 24404

Dennis Hamel

FORM CR-2/3 Rev. 01-84

MAY 16 1989 JUN 12 1989