

12-20

4-060483

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-22,749-50 50

SW NW SE /4 SEC. 05, 08 S, 17 W
1800 feet from S section line
2310 feet from E section line

Operator license# 5134

Lease Stamper well # 2-5

Operator: Graham-Michaelis Corporation

County Rooks

Address: P.O. Box 247
Wichita, Kansas 67201

Well total depth 3337 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1226 feet

108.45

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524-0347

Company to plug at: Hour: 1:30 P.M. Day: 20 Month: December Year: 93

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 210 sxs. 60/40 posmix - 10% gel - 12 sxs. gel and hulls.
Plug while pulling casing.

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1993
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 4:30 P.M., Day: 20, Month: December, Year: 93

Actual plugging report: 8 5/8" to 1226' w/425 sxs. 5 1/2" to 3333' with
165 sxs. Plug back to 3000' with sand and spot 5 sxs. cement with dump
bailer. Shoot and pull casing free at 1700'. Mix and pump 35 sxs.
cement with 100# hulls and displace to 1550'. Pull casing to 1300' and
pump 12 sxs. gel followed by 50 sxs. cement with 100# hulls and displace.
Pull casing to 600' and circulate cement with 80 sxs. Pull remaining
casing and top with 10 sxs.

Remarks: Allied cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1869 GL

I did not observe the plugging. Herb Deines

DATE 12-30-93
INV. NO. 39617

Herb Deines
(agent)