

6 040288

15-163-02981-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 15-163-19254-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134
Operator: Shaham Michaelis
Name & Address: 211 N. Broadway
Box 247
Wichita, Kansas 67202

_____ feet from S section line
_____ feet from E section line

Lease Name Stamper Well # B-1
County Rooks 113.75
Well Total Depth 3500' feet
Conductor Pipe: Size _____ feet _____
Surface Casing: Size 8 3/8 feet 252' w/165.44

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated Kelso casing Pulling

Plugging Contractor Allied Engr-Kelso Eng. License Number _____
Address Russell, KS. - Chase, KS.

Company to plug at: Hour: 11:00AM Day: 12 Month: 12 Year: 19 89

Plugging proposal received from Bob Brunnaman
(company name) Kelso Eng. (phone) _____

were: 5 1/2" @ 3400' w/150 sp. - Top. Perf. 3341
P.B. - 5 sp cmt, sand to 3300', 5 sp cmt. - slot @ 2700',
2500', Recovered 2013' of 5 1/2" csg. -

Ordered 225 sp 50/50 poz 8 gel, 25 sp gel, 6 sp hulls
Plugging Proposal Received by Dennis J. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00AM Day: 12 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT Loaded in 1 sp hulls, 5 sp gel w/hulls,
Rel. flag, 50 sp cmt. w/hulls, 15 sp gel w/hulls, 100 sp
cmt w/hulls, (flag stopped @ 620' - broke loose), -> 6 sp gel w/hulls,
(used total of 6 sp hulls), 75 sp cmt. 12-21-84
Max. P.S.I. 500[#] Shut-in 200[#]

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Dale Balthasar helped with flag data. DEC 21 1989
(If additional description is necessary, use BACK of this form.)

I (did) / did not) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

Signed Dennis J. Hamel
(TECHNICIAN)

DATE 1-18-85
INV. NO. 6327

12-20-84
4