

11-15 15-163-20779-00-00

4-30-78

6 041004

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SE SE SW, SEC. 8, T. 8, R. 17 W&E
feet from S section line
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8735
Operator: S and M Oil
Name & Address: 205 N. Jefferson
Plainville, Ks. 67663

Lease Name Schindler Well # 1
County Rooks 109.20
Well Total Depth 3360 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1269' w/400 sks circ

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement License Number

Address Russell, Ks.

Company to plug at: Hour: 8:30AM Day: 15 Month: Nov Year: 19 88

Plugging proposal received from Steve Crawford

(company name) S and M Oil (phone)

were: 5 1/2" casing set at 3359' w/175 sks. Top perf at 3307'. Plug bottom
w/sand to 3250' w/5 sks cement on sand. Rec 1853' of casing. Ordered 250 sks
65/35 Poz 10% Gel and 10 sks gel w/1/4# F.C. plus 5 sks Hulls. W.H.M. 1500'

RECEIVED
STATE CORPORATION COMMISSION
JAN 19 1989
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed Hour: 1:30PM Day: 15 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT

Pumped in 8 5/8" casing 250 sks cement w/1/4# F.C. plus
5 sks Hulls mixed in cement. Max 800# S.I. 500# psi.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-20-89

INV. NO. 23751

lib S.

Signed Dennis L. Hamel (TECHNICIAN)
Dennis L. Hamel

11-15 FEB 10 1989