

6 040830

11-23-87

API NUMBER 15-163-19120-00-07

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW NE SW, SEC. 12, T 8 S, R 17 W/E

_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Chesney Well # 302

Operator: Kaiser - Francis

County Rooks 108.84

Name & Address P.O. Box 666

Well Total Depth 3349 feet

Ellinwood, Ks. 67526

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 240' w/ 175 sx

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.J. Titan License Number _____

Address Hays, Ks.

Company to plug at: Hour: 9:00 AM Day: 23 Month: 11 Year: 19 87

Plugging proposal received from John Glenn

(company name) Kaiser - Francis (phone) _____

were: 5 1/2" set at 3348 w/ 225; D.V. at 1263' cmt. w/350 sx w/150 C.F. strata crete;

P.B. 3338' Perf at 3119 - 3331' K.C.

200 sx 60/40 poz 10 % gel w/ 1/4 # flo-cete and 6 sx hulls

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 AM Day: 23 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT

Ran tubg. to 3330', pump 40 sx cmt./ w/2 hulls; pulled tbg. to 2320', pump 40 sx cmt.

w/2 hulls: pulled tbg. to 1200' circ. cmt w/50 sx cmt and 2 sx hulls: Pulled tbg.

filled csg. and sq/ to 1000 #.

Received

Remarks:

(If additional description is necessary, use BACK of this form.)

JAN 07, 1988

INVOICED

(If ~~XXXXXX~~ observe this plugging.

DATE 1-11-88

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

INV. NO. 19483