

6 041165

3-19 233 R  
15-163-19112-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 13- 5-22-52

NE NW NW, SEC. 9, T 8 S, R 17 W

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245  
Okmar Oil Co.

Lease Name Arndts Well # 1

Operator Name & Address  
Box 723

County Rooks 109.88

Hays, Kansas 67601

Well Total Depth 3381 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 106 w/100

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor B J Titan License Number

Address Hays, Ks.

Company to plug at: Hour: 11:00PM Day: 19 Month: April Year: 19 90

Plugging proposal received from Bob Grant

(company name) Okmar Oil Co. (phone)

were: 5 1/2" casing set at 3380' w/100 sks. O.H. 3381. Perf anhy 1375; perf base

dakota 825. Perf at 105 to circ cement at surf. Ordered 350 sks 65/35 poz 10% gel w 1/4# f.c. plus 2 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:30 PM Day: 19 Month: Mar Year: 19 90

ACTUAL PLUGGING REPORT R.T.H. w/tubing to 1540'; pmpd 60 sks cement;

pulled tubing to 750'; pumped add 30 sks cement; cmt circ; P.O.O.H. w/tubing; Hooked up to 5 1/2" casing and sq add 235 sks cement. Max 1000#. S.T. 300#. (Bled off press after 1 hr.

to perf s.p. Perf base s.p. and pumped 25 sks cement to circ cement at surface.

Remarks: E1 1934

INVOICED

(If additional description is necessary, use BACK of this form.)

(old) observe this plugging.

DATE 5-9-90

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 28078