

4-032304

5-8

API NO. 15-163-013560000

API Number: 15- - 1954

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW NW NW /4 SEC. 09, 08, 17 W
4290 feet from S section line
4950 feet from E section line

Operator license# 5363

Lease: Arndts Well # 2

Operator: Berexco, Inc.

County: Rooks

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3388 ^{110.11} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 100 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Company Tools License# 5363

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 8 Month: May Year: 1998

Plugging proposal received from: Kevin

Company: Berexco, Inc. Phone: 785-628-6101

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order work string.

1998 Jun 3
RECEIVED
PLUGGING DIVISION
JUN 3 1998

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 6:00 P.M., Day: 8 Month: May, Year: 1998

Actual plugging report: 8 5/8" set at 100' w/100 sxs cwc. 5 1/2" set at 3384' with 100 sxs. Squeezed at 2353' w/250 sxs; 830' w/150 sxs. Holes in casing from 3194' to 3200'. Prod. Perfs 3100' - 3106'; 3194' - 3200'; 3154' - 3158'; 3256' - 3261'; 3278' - 3282'. Ran workstring to retrieve loc set packer. Ran workstring back in to plug. Mixed and pumped down 2 3/8" with 275 sxs cement blend with 500# hulls mixed in to circulate. Pulled tubing and tied onto 5 1/2". Squeezed with 25 sxs cement blend to Max. P.S.I. 500#. Held. Used total 300 sxs cement with 500# hulls. Squeezed 8 5/8" with 5 sxs cement blend to 500#. Held. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GO

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE JUN 08 1998

INV. NO. 50678

5-8

SEP 18 1998