

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22, 04600-002

NE-NE-SW, Sec. 12, T 8 S, R 170 E

2970 feet from N/S section line

2970 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5068

Lease Name CHESNEY Well # B-1

Operator Name & Address: THOMAS E. BLACK d/b/a
BLACK PETROLEUM CO.
527 UNION CTR. BLDG.
WICHITA, MO. 67202

County ROOFS.

Well Total Depth 3411 feet 4110.86

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor B+B DRIG. INC License Number 5110

Address 515 UNION CTR. BLDG. WICHITA, MO. 67202

Company to plug at: Hour: 3:00 AM Day: 3 Month: JUNE Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO JOHN ARMSTRONG

(company name) B+B DRIG. INC. (phone) 316-264-9342

were: 8 5/8" - 251 FT SP. CUL W/150 ST COMMON - 2% GEL - 3% CA-CL. (ALLIED)
ORDER - 200 ST 50% Formix 6% GEL - 3% CA-CL. & 8 5/8" OULG
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
DID PENETRATE ARBUCKLE - ELY. 1885 - ANH 1188. FT

Signed [Signature]
(TECHNICIAN) (BOIC)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:00 AM Day: 3RD Month: JUNE Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 200 ST 50% Formix 6% GEL - 3% CA-CL. AND 8 5/8" PLUG
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS
1ST PLUG @ 3330 FT W/20 ST CNT., 2ND PLUG @ 1200 FT W/20 CNT.
3RD PLUG @ 1758 FT W/100 ST CNT. 4TH PLUG @ 270 FT W/40 ST CNT.
5TH PLUG ^{SOLID BRIDE} HUIS-PLUG @ 410 FT W/10 ST CNT., 10 ST IN RAT HOLE (PIC)

Remarks: (Cemented By Allied cnt.)

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ / did not observe this plugging.

Signed [Signature]
(TECHNICIAN)

INVOICED
DATE 6-16-83
INV. NO. 4585-W

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1983
JUN 13 1983

FORM CP-2/3
Rev. 9-82