

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION  
Please TYPE Form and File ONE Copy

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 19 2006  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 07701016 -- 00-0602 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 1958.

Well Operator: VAL Energy Inc. KCC License #: 5822  
(Owner / Company Name) (Operator's)

Address: 200 W. Douglas #520 City: Wichita

State: Kansas Zip Code: 67202 Contact Phone: ( 316 ) 263 - 56688

Lease: R. Gerberding Well #: 2 Sec. 36 Twp. 33S S. R. 6W  East  West

S2 NE/4 - SE/4 - NW/4 - \_\_\_\_\_ Spot Location / QQQQ County: Harper

3497 ~~4650~~ Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2979 ~~2310~~ Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # 46  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 320 Cemented with: surface Sacks

Production Casing Size: 5 1/2 Set at: 4457 Cemented with: 125 TOC 3855' Sacks

List (ALL) Perforations and Bridgeplug Sets: Spot 50 sx cement plug at 3550', Perf casing @ 400' and cement to surface

Elevation: 1275 ( G.L. /  K.B.) T.D.: 4463 PBDT: 3550 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 4457-63 OH, Squeezed on 5-9-64 @ 3840' w/100sx., BP @ 4365' Perf @ 3788-92, Squeezed 9-9-04 3788-92 s/150 sx., Drilled outside of casing @ 4250', BP @ 3550, Perf 3502-04, Pressured to 3000 psi, No Breakdown, Held 3000 psi 24 hrs.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Todd Allam

Phone: ( 316 ) 263- - 6688

Address: 200 W. Douglas #520 City / State: Wichita, Ks. 67201

Plugging Contractor: Leiker Well Service KCC License #: 30891  
(Company Name) (Contractor's)

Address: Great Bend, Ks. Phone: ( 620 ) 793 - 2336

Proposed Date and Hour of Plugging (if known?): unknown due to rig schedule

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5-19-2006 Authorized Operator / Agent: Todd Allam  
(Signature)



CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Val Energy, Inc.  
200 W Douglas Ave., Ste 520  
Wichita, KS 67202-3005

May 19, 2006

Re: GERBERDING #2  
API 15-077-01016-00-00  
NESENW 36-33S-6W, 1650 FNL 2310 FWL  
HARPER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000

Sincerely

A handwritten signature in dark ink, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor