

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 097-21147 --00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 07-13-1985.

Well Operator: H & B Petroleum Corporation KCC License #: 32158  
(Owner / Company Name) (Operator's)  
Address: PO Box 277 City: Ellinwood  
State: Kansas Zip Code: 67526-0277 Contact Phone: ( 620 ) 564 - 3002  
Lease: Wedel Well #: 1 Sec. 14 Twp. 29 S. R. 18  East  West  
C - SW - SE - Spot Location / QQQQ County: Kiowa

660 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)  
1980 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8 5/8" Set at: 433' Cemented with: 350 Sacks  
Production Casing Size: 4 1/2" Set at: 4852' Cemented with: 175 Sacks  
List (ALL) Perforations and Bridgeplug Sets: 3484-3488 squeezed 4713-4718 4723-4730 4848-4852 open hole 4852-4864

Elevation: 2173 ( G.L. /  K.B.) T.D.: 4864 PBTD: 4864 Anhydrite Depth: 1150  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):  
Squeeze 4700 to TD with 100 sacks 60/40 pos. Plug at 1150 with 15 sacks gel & 50 sacks 60/40 pos. Plug at 460 with 50 sacks 60/40 pos.  
Plug at 40, cement to surface. Will try to recover 2000' of pipe.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations: Al Hammersmith  
Phone: ( 620 ) 564 - 3002  
Address: PO Box 277 City / State: Ellinwood, Kansas  
Plugging Contractor: Xtreme Well Service, Inc. KCC License #: 33369  
(Company Name) (Contractor's)  
Address: PO Box 337, Ellinwood, Kansas 67526 Phone: ( 620 ) 564 - 2094

Proposed Date and Hour of Plugging (if known?): 06-23-06 8:00 a.m.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent  
Date: 06-08-06 Authorized Operator / Agent: [Signature]  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JUN 09 2006  
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

H & B Petroleum Corp.  
130 E. Ross, Suite 103  
Clearwater, KS 67026

June 16, 2006

Re: WEDEL #1  
API 15-097-21147-00-00  
SWSE 14-29S-18W, 660 FSL 1980 FEL  
KIOWA COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely

  
David P. Williams  
Production Supervisor