

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

Lease Operator: American Warrior Inc.  
 Address: P.O Box 399 Garden City Kansas 67846  
 Phone: (620 ) 272 - 1023 Operator License #: 4058  
 Type of Well: O&G oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 5/30/06 (Date)  
 by: Steve Durrant (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
Mississippian Depth to Top: 5998' Bottom: 6126' T.D. 6423'  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 119-20319 - 00 - 00  
 Lease Name: Merkle  
 Well Number: 2-7  
 Spot Location (QQQQ): C - S2 - NW - NW  
4290' Feet from  North /  South Section Line  
4620 Feet from  East /  West Section Line  
 Sec. 7 Twp. 35 S. R. 28  East  West  
 County: Meade  
 Date Well Completed: 11/8/78  
 Plugging Commenced: 6/1/06  
 Plugging Completed: 6/1/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
5998' to 6126'	oil and gas	1517'	surface	85/8	1517'	0
		6416'	surface	41/2	6416'	1530'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Had log Tech set CIBP at 5900' and cut 41/2 casing off at 1530'. Pumped 15sx gel and 50sx plug. Pull 41/2 to 690' pumped 40sx, pulled 41/2 to 300' and pumped 40sx plug, pulled 41/2 to 40' and pumped 20 sx plug cement circulated

**RECEIVED  
JUN 12 2006  
KCC WICHITA**

Name of Plugging Contractor: American Warrior Inc. Allied Cement Co. License #: 4058 99996  
 Address: P.O.Box 399 Garden City 67846

Name of Party Responsible for Plugging Fees: American Warrior Inc.  
 State of Kansas County, Finney, ss.

Joe smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]  
 (Address) P.O. Box 399 Garden City Kansas 67846

**ERICA KUHLMIEIER**  
 Notary Public - State of Kansas  
 My Appt. Expires 09-12-09

SUBSCRIBED and SWORN TO before me this 8 day of June, 20 06  
[Handwritten Signature] My Commission Expires: 09-12-09  
 Notary Public

*per*