

Notar: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CI
December 2006
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Jack Horton

Address: 1167 Rd. 14

Phone: (620) 249-4476 Operator License #: 31486

Type of Well: SWD Docket #: E10442
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 5-10-06 (Date)

by: Larry Marchant (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Weiser Depth to Top: 715 Bottom: 730 T.D. 750

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-125-01274-00-00

Lease Name: Hecht

Well Number: 7

Spot Location (QQQQ): S2 - S2 - NE - SE

1520 Feet from ☐ North / ☒ South Section Line

660 Feet from ☒ East / ☐ West Section Line

Sec. 16 Twp. 34 S. R. 14 ☒ East ☐ West

County: Montgomery

Date Well Completed: N/A

Plugging Commenced: 5-26-06

Plugging Completed: 5-26-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Weiser	Oil and Gas	750	Surface	4.5		RECEIVED KCC DISTRICT #3 JUN 08 2006 CHANUTE, KS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1 inch to 750 ft. Mixed 5 bbl gel water, spotted 10 sacks of cement with cotton seed hulls on bottom. Pulled 1 inch up to 350 feet, circulated 35 sacks of cement to surface, pulled 1 inch out.

Name of Plugging Contractor: Elmore's Inc. License #: 32884


Address: Box 87 Sedan, KS 67361

Name of Party Responsible for Plugging Fees: Jack Horton

State of Kansas County, Chautauqua, ss.

Jack Horton

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]

(Address) 1167 Rd. 14 Sedan, KS 67361

SUBSCRIBED and SWORN TO before me this 8th day of June, 2006

RECEIVED

JUN 14 2006

KCC WICHITA

[Signature]
Notary Public

My Commission Expires: 4-8-2010

[Signature]

CHANUTE, KS

STATEMENT

ELMORE'S INC.
Box 87 • 776 HWY 236
Gedon, NE 67361
Call: (620) 244-2519
Eve: (620) 725-5538

5-26-06

Customer Jack Horton
Address _____
City _____ State _____ Zip _____

Qty.	Description	Price	Amount
45	Sks Cement	7.50	337.50
1 1/2	hr Cement Pump	60.00	90.00
1	Bank Tank (1 1/2 Rins)	60.00	30.00
			457.50
		Tax	29.42
	Hecht # 7		\$ 486.92
	Ran 1" To 7.50'		
	Mixed 5 BR2 Cool Water		
	Roasted 10.9ks Cement		
	With Cotton Seed in 1/2 in. water		
	Pulled 1" Into 350' Circulated		
	35 cks "Cement" To Surface		
	Pulled 1" Out		

RECEIVED

JUN 14 2006

KCC WICHITA

Thank You - We appreciate your business!

Rec'd. by

TERMS: Account due upon receipt of services. A 14-95 Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

