

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER NA 15-091-19153-00-00
NWNENW Sec/Twp/Rge 32/13S/23E
GPS 5199 feet from south section line
GPS 3678 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Funds

Lease/Well# JOHNSON COUNTY REC. #1
County JOHNSON

Name & _____
Address _____

Well Total Depth 228 feet
Production Pipe: 2" Size Feet 228 EST.
Surface Casing: 7" Size Feet _____

AB oil well _____ Gas Well X SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE LLC Lic. # 33749

Address: 19245 FORD ROAD CHANUTE KANSAS 66720

Company to plug at: Hour: 9:00 AM Day: _____ 1 Month: MAR 2006

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE Phone: 620-431-9212

Were: FILL INSIDE AND OUTSIDE WITH CEMENT FROM BOTTOM TO SURFACE.

Plugging Proposal Received by: TAYLOR HERMAN

Plugging attended by Agent: All X Part _____
TECHNICIAN
None _____

Operations Completed: Hour: 12:00PM Day: _____ 1 Month: MAR 2006

Actual Plugging Report: RAN 1" ON OUTSIDE OF 2" PRODUCTION CASING AND FOUND

BOTTOM AT 175'. WASHED OUTSIDE DOWN TO 177' AND HIT SOLID. CIRCULATED CEMENT FROM
BOTTOM TO SURFACE ON OUTSIDE. RAN 1" INSIDE 2" PRODUCTION CASING AND FOUND BOTTOM A
225'. WASHED INSIDE DOWN TO 228' AND HIT SOLID. CIRCULATED CEMENT FROM BOTTOM TO
SURFACE. TOTAL OF 65 SACKS OF CEMENT USED.

Remarks: CONTROL# 20060044 LEASE NAME: JOHNSON COUNTY REC. WELL# JOCORE 1
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: TAYLOR HERMAN
TECHNICIAN

RECEIVED
MAR 22 2006
KCC WICHITA

Taylor C. Herman

PH