

3 022980

15-001-020460000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001--041

NW,NW,NE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.

4954 feet from south section line

2119 feet from east section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 101-400-Operator: STATE OF KANSAS Fee Fund

Name &amp; \_\_\_\_\_

Address \_\_\_\_\_

AB oil well X Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KEPLEY WELL SERVICE, LLCLic. # 30670Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 9:00A.M. Day: 21 Month: 12 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HADBEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TOCIRCULATE THE 2" CASING FULL OF CEMENT.Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_

TECHNICIAN

None XOperations Completed: Hour: 11:00A.M. Day: 21 Month: 12 2005Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 820'.CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROMTHE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENTWAS FILLED FROM SURFACE. 25 SACKS OF CEMENT WERE PUMPED INTOTHIS WELL.Remarks: ( GPS SESSION PT. NO.4.)( WELL NO. 15. API NO. 15-001-27-96400-00)(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN

RECEIVED

JAN 09 2006

KCC WICHITA

Bene