

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23174-00-00
Spot: NESWNE Sec/Twnshp/Rge: 21-8S-25W
1795 feet from N Section Line, 1875 feet from E Section Line
Lease Name: BABCOCK TRUST Well #: 1-21
County: GRAHAM Total Vertical Depth: 4250 feet

Operator License No.: 31790
Op Name: FREMONT EXPLORATION, INC.
Address: 12412 ST. ANDREWS DRIVE
OKLAHOMA CITY, OK 73120

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		

\$ 138.13

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/09/2006 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: CHUCK RHOADES Company: FREMONT EXPLORATION, INC. Phone: (405) 936-0012

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 06/09/2006 12:15 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2125' w/25 sxs.
2nd. Plug at 1250' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:


INVOICED

DATE: 6-15-06
SER. NO.: 2006061790

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 
(TECHNICIAN)

JUN 13 2006

RECEIVED
JUN 14 2006
KCC WICHITA

PET