

3 022990

15-001-02055-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001--039

SE NE,NW,NE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.

4908 feet from south section line

1542 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License #

100 101

Lease/Well# JONES NO.4

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 927" feet

Name &

Production Pipe: 2" Size Feet 900

Address

Surface Casing: 7" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670-33749

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00A.M. Day: 2 Month: 1 2006

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 900"

THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING

PROPOSAL WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

Part

X

TECHNICIAN
None

Operations Completed: Hour:

12:00P.M. Day:

2 Month:

1

2006

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 875'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING

AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM

SURFACE. 33 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.2.) (THIS WAS WELL NO.4 ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

JAN 19 2006

KCC WICHITA