

3 023051

15-001-02101-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050052-010
SE SW, SE, SW 1/4 Sec/Twp/Rge S.8-T.26S.-R.18E.
279 feet from south section line
3612 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 100 101
Operator: STATE OF KANSAS
Name & FEE FUND PLUGGING
Address

Lease/Well# NELSON NO.10
County ALLEN
Well Total Depth 750 feet
Production Pipe: 2" Size Feet 750
Surface Casing: 7" Size Feet 20'

AB oil well Gas Well SWD Well/ Input Well D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE Lic. # 6372

Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:30A.M. Day: 5 Month: 4 2006

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT
HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THS PLUGGING PROPOSAL
WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part TECHNICIAN
None X

Operations Completed: Hour: 11:00A.M. Day: 5 Month: 4 2006

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 750'. CEMENT
WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT
SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.
29 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
APR 17 2006
KCC WICHITA

Remarks: (GPS SESSION PT. NO.10) (NO OTHER NUMBER IS AVAILABLE FOR THIS WELL.)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

Handwritten initials/signature in the bottom right corner.