

3 023052

15-001-02102-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

CONTROL NO. 20050052-011

SE NW, SE, SW 1/4 Sec/Twp/Rge S.8-T.26S.-R.18E.

768 feet from south section line

3612 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 100 101Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____Lease/Well# NELSON NO.11County ALLENWell Total Depth 750 feetProduction Pipe: 2" Size Feet 750Surface Casing: 7" Size Feet 20'

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE Lic. # 6372Address: P.O. BOX 386, CHANUTE, KANSAS 66720Company to plug at: Hour: 11:00A.M. Day: _____ Month: 4 2006Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THATHAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THS PLUGGING PROPOSALWAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All _____ Part _____ TECHNICIAN
None ☒Operations Completed: Hour: 4:30P.M. Day: _____ 5 Month: 4 2006Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 750'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING ATSURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.29 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.RECEIVED
APR 17 2006
KCC WICHITARemarks: (GPS SESSION PT. NO.11) (NO OTHER NUMBER IS AVAILABLE FOR THIS WELL.)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN