

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25540-00-00
Spot: NENWNWSW Sec/Twnshp/Rge: 27-14S-19W
2580 feet from S Section Line, 360 feet from W Section Line
Lease Name: HERTEL KRAUS UNIT Well #: 1
County: ELLIS Total Vertical Depth: 3875 feet

Operator License No.: 33625
Op Name: HERTEL OIL COMPANY LLC
Address: 704 EAST 12TH ST.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	238		

\$ 125.94

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/06/2006 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: HERTEL OIL COMPANY LLC Phone: (785) 628-2445

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 06/06/2006 1:15 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3800' w/25 sxs.
2nd. Plug at 1475' w/25 sxs.
3rd. Plug at 750' w/100 sxs.
4th. Plug at 280' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:


INVOICED
DATE 6-15-06
2006061792

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

RECEIVED

JUN 14 2006

KCC WICHITA

JUN 13 2006

PKT