

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21005-00-00
Spot: SWNW Sec/Twnshp/Rge: 16-35S-34W
1980 feet from N Section Line, 660 feet from W Section Line
Lease Name: BOLES Well #: 3-16
County: SEWARD Total Vertical Depth: 6800 feet

Operator License No.: 9228
Op Name: MARLIN OIL CORPORATION
Address: PO BOX 14630
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6270		WITH 2 SX CMT
CIBP		6335		
DVT		4596		
PROD	4.5	6796	1047	WITH 275 SX CMT
SURF	8.625	1701		WITH 825 SX CMT

\$ 221.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/26/2006 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: JOEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 6270' WITH 2 SX CMT. PLUG AT 1730' WITH 50 SX CMT. PLUG AT 660' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/30/2006 10:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

8 5/8" SQUEEZED AT 1520' WITH 75 SX CMT. CIBP @ 6270 WITH 2 SX CMT. TOP OF 4 1/2" CASING STUB AT 1047'. PUMP 60 SX CMT AT 1732' IN 4 1/2" CASING. FULL RETURNS DECREASING TO MINIMAL RETURNS ON DISPLACEMENT. TRIP IN HOLE WITH 2 3/8" TUBING TO 900' & SPOT 50 SX CLASS C CMT WITH 3% CC. NO RETURNS. TRIP OUT OF HOLE WITH TUBING. 5/30/06: RUN IN HOLE WITH TUBING. TAG TOC @ 875'. PULL OUT OF HOLE TO 650'. LOAD HOLE & PUMP 40 SX CMT. PULL OUT OF HOLE TO 60' & PUMP 20 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
6404	6410		
6343	6358		
6320	6326		

INVOICED
DATE 6-15-06
2006061795

Remarks: USED CLASS C CMT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01



Signed Jim Holland PART II
(TECHNICIAN)

RECEIVED
JUN 14 2006
KCC WICHITA

Form C-1

PCY