

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20392-00-01
Spot: SWSENE Sec/Twnshp/Rge: 29-9S-24W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: HOETING UNIT Well #: 2-5
County: GRAHAM Total Vertical Depth: 4098 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4131		
SURF	8.625	266		

#133.19

Well Type: EOR UIC Docket No: E19789.1 Date/Time to Plug: 06/13/2006 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs Swift Multi-Density Cement.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 06/13/2006 2:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Perforated casing at 2250' and 1100'.
Ran tubing to 2298' and circulated cement to surface with 85 sxs SMD with 300# hulls.
Pulled tubing and tied onto production casing - mixed and pumped 45 sxs SMD cement with 125# hulls.
Max. P.S.I. 400#. S.I.P. 300#.
Tied onto annulus and pumped 60 sxs SMD cement with 75# hulls.
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

INVOICED
6-15-06
2006061798

Remarks: LEASE ORIGINALLY KNOWN AS GEO NICKELSON #5-RENAMED HOETING UNIT 2-5 WHEN FIELD UNITIZED. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed 
RECEIVED (TECHNICIAN)

JUN 15 2006
KCC WICHITA

JUN 14 2006

DON E. PRATT #5 GEO. NICKELSON 29-9-24W
 HAYS, KANSAS SW SE NE
 CONTR L. J. DREILING & SONS CTY GRAHAM

GEOLOGIST J. R. GREEN FIELD HOETING

E 2537 KB CM 11/10/70 CARD ISSUED 1/7/71 IP P 91 BOPD + TR WIR
 LKC 4014-18, 4034-38
 4052-56 & 4071-76

API 15-065-20,392

LOG	TOPS	DEPTH	DATUM	
				8 5/8" 266/190sx; 4 1/2" 4131/200sx
*ANHY	2199	+ 338		DST(1) 3870-3946/30-30-30-30, 1360'SW,
*B ANHY	2235	+ 302		BHP 1027-1004#/30", FP 161-810#
TOP	3619	-1082		DST(2) 3998-4087/30-30-30-30, 300'GIP,
HEEB	3837	-1300		180'o & GCM, 180'HG & MCO, BHP 727-
TOR	3860	-1323		688#, FP 104-282#
LKC	3873	-1336		MICT, COTD, PF 4071-76, 4052-56, 4034-
BKC	4104	-1567		38, 4014-18 FU 900'OIL/12HRS AC(EACH ZN)
LTD	4149	-1612		3000 SD/24 FU 2600'FL SWB 103BF, SWB 16
RTD	4150	-1613		BOPH 900'OB/3HRS, POP
*DRILLERS	TOPS.			

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS