

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24495-00-00
Spot: SWSE Sec/Twnshp/Rge: 1-16S-26W
660 feet from S Section Line, 1800 feet from E Section Line
Lease Name: ROBERT TURNER Well #: 1
County: NESS Total Vertical Depth: 4503 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	217		WITH 160 SX CMT

\$ 14635

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/24/2006 12:00 PM
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.
Proposal Rcvd. from: CAROL NICHOLS Company: MALLARD, J. V., INC. Phone: (620) 241-4640

Proposed Plugging Method: 1ST PLUG AT 2000' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 50 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 05/24/2006 2:15 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 2000' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 50 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.


Perfs:

INVOICED
DATE 6-15-06
SERIAL 2006001799

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed Steve Durrant
(TECHNICIAN)

RECEIVED
JUN 14 2006
KCC WICHITA

PCT