

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-087-19016-00-01
Spot: NWNWNWSE Sec/Twnshp/Rge: 17-9S-20E
2334 feet from S Section Line, 2357 feet from E Section Line
Lease Name: MCCLOUTH GAS STORAGE Well #: 0-1
County: JEFFERSON Total Vertical Depth: 1437 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HIGHWAY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	1420		330 SX
SURF	12.75	19		8 SX

\$ 46.70

Well Type: GSI UIC Docket No: _____ Date/Time to Plug: 04/27/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: BERNIE ROCKERS Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO TOTAL DEPTH. PLUG SOLID WITH CLASS A CMT. CUT CASING 4' BELOW SURFACE. BACKFILL AND RECLAIM SITE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

Ran 2 7/8" tubing to bottom and pumped 60 sacks of calcium chloride cement. Pulled tubing to 1200' and circulated 196 sacks of cement to surface. Hooked on to swedge and squeezed cement to surface to fill in displaced cement.

RECEIVED
KCC DISTRICT #3

MAY 25 2006 TH

CHANUTE, KS

RECEIVED
JUN 12 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman
(TECHNICIAN)

INVOICED
DATE June 13, 2006
WT. NO. 2006061783