

OCT 16 1970

CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

10-16-70

15-179-20271-00-00

OPERATOR:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	HESKETT #1
LOCATION:	NW SW SE, Sec. 1-7S-26W Sheridan County, Kansas
GEOLOGIST:	Jack K. Wharton
SPUD DATE:	October 2, 1970
COMPLETION DATE:	October 10, 1970

0	100	Surface soil & clay
100	185	Sand
185	365	Shale
365	575	Shale & Shells
575	1410	Shale & Sand
1410	1840	Shale
1840	2010	Sand
2010	2108	Shale
2108	2425	Shale (Red Bed)
2425	2769	Shale
2769	2830	Shale & Lime
2830	2985	Shale
2985	3686	Lime & Shale
3686	3873	Lime
	3873	R. T. D.

Set 8-5/8" new, 20# csg. at 353' w/250 sx. Sunset cement. Cement circulated. Plug was down at 7:00 a.m. 10-2-70.
Dry and Abandoned

<u>SAMPLE TOPS</u>	<u>ELEVATION</u>
Anhydrite 2202 (+368)	2570 K.B.
B/Anhydrite 2235 (+335)	2568 D.F.
Heebner 3656 (-1086)	2561 G.L.
Toronto 3679 (-1109)	
Lansing 3694 (-1124)	

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the HESKETT #1, NW SW SE, Sec. 1-7S-26W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
Jerry A. Langrehr
President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 14th day of October, 1970.

Sue J. McCoy
Sue J. McCoy, Notary Public

My Commission Expires:

November 1, 1973