

Operator
Rains & Williamson Oil Co., Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry Hole

Well No. #1 Lease Name Cersovsky

S 10 T7S R 33 ^{EX}
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 4058-4135, 30 (30) 60 (30). Rec. 2100' saltwater. FP's 264, 747. IBHP 1227, FBHP 1227. Temp. 112°.			<u>E. LOG TOPS</u>	
			Wabaunsee	3756 (-599)
			Howard	3850 (-693)
			Topeka	3898 (-741)
			Heebner	4083 (-926)
			Toronto	4114 (-957)
			Lansing	4130 (-973)
			BKC	4385 (-1228)
			Marmaton	4431 (-1274)
			Ft. Scott	4514 (-1357)
			Cherokee Sh.	4600 (-1443)
			Cherokee Sd.	4664 (-1507)
			Miss.	4754 (-1597)
			<u>LTD</u>	4820 (-1663)
DST #2 - 4121-4205, 30 (30) 60 (30). Rec. 2100' muddy water. FP's 158-654. IBHP 1310, FBHP 1310. Temp. 112°.				
DST #3 - 4663-4721, 30 (30) 60 (30). Rec. 2580' saltwater. FP's 840-1200, 1310-1310. IBHP 1340, FBHP 1390. Temp. 117°.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wilson Rains
Wilson Rains

Signature

President

Title

3-19-81

Date