

15-163-00112-00-00


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - C. U. BAY
Farm - Hunter No. 1

SEC. 4 T. 8 R. 17W
SW SW SW

Total Depth. 3399'
Comm. 3-29-48 Comp. 5-21-48
Shot or Treated. Acidized
Contractor. Virginia Drilling Co., Inc.
Issued. 7-24-48

County. Rooks KANSAS



Elevation. _____

Production. Pot. 87 BO & 60% wtr

CASING:

8-5/8" 193'
5-1/2" 3385' 100 Saf cement

Figures Indicate Bottom of Formations.

lime	0-60
sand & shale	150
shale	193
shale & shells	440
sand	525
shale & shells	640
sand	700
shale & shells	795
sand	905
shale, shells & pyrite	1035
shale & shells	1266
anhydrite	1306
shale, lime & iron	1520
shale & shells	1618
shale, shells & salt	1750
shale & shells	1820
lime	1840
shale & lime	2350
lime brkn	2420
lime & shale	2905
lime	3005
shale & lime	3045
lime	3120
lime & shale	3148
lime	3300
lime & shale	3360
shale brkn	3384
Arbuckle lime RTD	3388
dolomite	3399
Total Depth	

Tops:	
Topeka	2853
Lansing	3101
Arbuckle	3384

DP-DD-3390-VSSO-DD 3392.
2 bbls acid on bottom. Bailed
1 1/2 BOPH-500A-DD 3399-1 BOPH
from 3396-98-1500A-Swab 4 BOPH.

Circulate:
2 hrs. @ 3005
1 hr @ 3015
1 hr. @ 3045
1 hr. @ 3055
1 hr. @ 3110
1 1/2 hrs. @ 3145
1 1/4 hrs. @ 3205
1 hr. @ 3235
1 hr. &
13 min. @ 3263
1 hr. @ 3283
1 hr. &
13 min. @ 3342
2 hrs. @ 3388

PLUGGING
FILE SEC 4 T. 8 R. 17W
BOOK PAGE 112 LINE 41

STATE DEPARTMENT OF GEOLOGY
WICHITA, KANSAS
1257
CONSERVATION