

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25390-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 23-14S-17W  
890 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: J & A Well #: 1  
County: ELLIS Total Vertical Depth: 3575 feet

Operator License No.: 9860  
Op Name: CASTLE RESOURCES, INC.  
Address: BOX 87  
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3575	1980	w/125 sxs cmt
SURF	8.625	215	0	150 SX CMT

\$ 116.19

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/13/2006 4:00 PM  
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE  
Proposal Rcvd. from: RON GEIST Company: GEIST, RON DBA WILDCAT WELL Phone: (785) 432-4000

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Cut casing loose at 1980'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/13/2006 10:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded off bottom to 3445' and topped with 5 sxs cement using a dump bailer.  
Cut casing loose at 1980'.  
Pulled up to 1825' - mixed and pumped 125 sxs cement with 200# hulls.  
Pulled up to 1200' - spotted 40 sxs cement with 200# hulls.  
Pulled up to 550' - spotted 30 sxs cement.  
Pulled up to 150' and circulated cement with 35 sxs.  
POOH. Hole full of cement.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

**INVOICED**  
DATE 6-21-06  
TEL NO. 2006061825

District: 04

Signed Jay Pfeifer  
(TECHNICIAN)

JUN 14 2006

RECEIVED  
JUN 21 2006  
KCC WICHITA

POST

WILDCAT  
 SCHOENCHEN

CASTLE RESOURCES  
SCHOENCHEN KS 67667

WILDCAT

23-14S-17W  
100'N, C SW NW NE

#1 J & A

site: 1-1/4 S & 1 W OF VICTORIA KS  
 contr: ANDERSON DRILLING #1  
 geol: JERRY GREEN

cty: ELLIS API 15-051-25390  
 field: WC (3/4 NE OF HERL NE)


fr date 01/31/2005    spd date 02/14/2005    drig comp 02/21/2005    card issued 06/27/2005    last revised 07/25/2005

ELV: 1971 KB, 1966 GL LOG

tops.....	depth/datum
ANH.....	1134 +837
B/ANH.....	1170 +801
HEEB.....	3198 -1227
TOR.....	3218 -1247
LANS.....	3246 -1275
BKC.....	3472 -1501
ARB.....	3502 -1531
PBTD.....	3535 -1564
RTD.....	3573 -1602
LTD.....	3575 -1604

**IP status**  
**DELAYED COMP, 05/15/2005**  
 NOTE: CORR & INFO REL 7/25/2005 - CORR CSG; CORR  
 RTD (WAS 3590); WAS TEMP ABD  
 CSG: 8-5/8" 215 / 150 SX (ALT 2), 5-1/2" 3575 / 125 SX  
 NO CORES  
 DSTS TAKEN - DETAILS NA  
 TRGT ZN: ARB (OIL), PTD 3600 (ARB), MICT - CO, PB 3535,  
 PF (ARB) 3540-3544, W / 4 SPF, SWB DWN, NAT, NS, SQZ' D  
 PFS W/50 SX CMT, CO CMT, PF (ARB) 3502-3504, 3508-3512,  
 3518-3520, 3522-3526, W / 4 SPF, AC 10,000 GAL (20%), SWB  
 LD, SO, NO TBG RUN, POP, IPP 10 BO & 400 BW/24 HRS,  
 TOO MUCH WTR; NO OIL SOLD, SI - LOOKING FOR SWD  
 TO USE FOR DISPOSAL OF WTR; DELAYED COMP  
 5/15/2005 - NO OTHER INFO AVAILABLE - TEMP COMP  
 7/25/2005

COPYRIGHT 2005  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS