

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20089-00-01
Spot: NENE Sec/Twnshp/Rge: 8-30S-19W
4615 feet from S Section Line, 662 feet from E Section Line
Lease Name: ROGERS C Well #: 1
County: KIOWA Total Vertical Depth: 5295 feet

Operator License No.: 32158
Op Name: H & B PETROLEUM CORP.
Address: 130 E. ROSS, SUITE 103
CLEARWATER, KS 67026

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5000		WITH 4 SX CMT
PROD	4.5	5294	1420	
SURF	9.625	470		

\$ 172.09

Well Type: SWD UIC Docket No: D16038.0 Date/Time to Plug: 06/16/2006 12:45 PM

Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.

Proposal Rcvd. from: AL HAMMERSMITH Company: H & B PETROLEUM Phone: (620) 584-6380

Proposed Plugging Method: CIBP @ 5000' & 4 SX CMT. PLUG AT 1420' WITH 80 SX CMT. PLUG AT 1200' WITH 75 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/16/2006 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 5000' & PUT 4 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 1420' WITH 80 SX CMT. 2ND PLUG AT 1200' WITH 300# HULLS IN WITH 15 SX GEL GEL & 200# HULLS IN WITH 75 SX CMT. 3RD PLUG AT 480' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5104	5235		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

INVOICED
DATE: 6-21-06
BILL NO. 2006061827

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
JUN 21 2006
KCC WICHITA

Form CP-2

PKT