

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-01270-00-01
Spot: NWNWNWSW Sec/Twnshp/Rge: 35-34S-14E
2440 feet from S Section Line, 5080 feet from E Section Line
Lease Name: RUSSELL R J Well #: 2
County: MONTGOMERY Total Vertical Depth: 1090 feet

Operator License No.: 33074
Op Name: DART CHEROKEE BASIN OPERATING
Address: 600 DART RD PO BOX 177
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	10	20		
PROD	2.875	1085	0	
SURF	7	286	0	

\$ 35.43

Well Type: SWD UIC Docket No: D20408.0 Date/Time to Plug: 05/23/2006 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 331-7870

Proposed Plugging Method: Run a 1" cement string to TD and fill well from bottom to top.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 05/23/2006 12:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Ran 1" pipe inside casing to 700', hit hard. Ran 1" pipe between casing and surface pipe to 400'. Filled well from bottom to top with cement. Pulled out 1" and topped off well. A total of 133 sacks of Portland cement were used to plug this well.

Perfs:

RECEIVED
KCC DISTRICT #3

JUN 14 2006 *Amb*

CHANUTE, KS

RECEIVED
JUN 19 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning

(TECHNICIAN)

INVOICED
DATE 6-21-06
2006061819

per