

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22414-00-00
Spot: N2N2NW Sec/Twnshp/Rge: 24-19S-13W
4950 feet from S Section Line, 3960 feet from E Section Line
Lease Name: SCHARTZ Well #: 2
County: BARTON Total Vertical Depth: 3550 feet

Operator License No.: 7023
Op Name: KLIMA WELL SERVICE, INC.
Address: 610 WEST FRONT STREET
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3430	0	w/175 sxs cmt
SURF	8.65	344	0	w/250 sxs cmt

115.38

Well Type: SWD UIC Docket No: D21287.0 Date/Time to Plug: 06/08/2006 1:00 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DON BROWNING Company: KLIMA WELL SERVICE, INC. Phone: (620) 786-7063

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 1000# hulls. Brought 420 sxs. Log Tech perf at 722' and 1250'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2006 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Klima Well Service RIH with tubing to 2200'.
Copeland rigged to tubing and pumped 100 sxs 60/40 pozmix with 300# hulls mixed in - no returns.
Pulled tubing to 1300'. Copeland rigged to tubing and pumped 100 sxs cement with 200# hulls. No returns - let set two hours.
Pulled tubing. Re-ran tubing to 1300'.
Rigged to tubing and pumped 75 sxs cement with 200# hulls - mixed in to circulate cement to surface.
Pulled tubing - rigged to 4 1/2" casing and pumped 30 sxs cement.
Max. P.S.I. 600#. S.I.P. 600#.
Backside full of cement - visual check - 4 1/2" cemented into 8 5/8" casing.

Perfs:

Top	Bot	Thru	Comments
3435	3550	OH	


Remarks: COPELAND ACID SERVICES-TICKET #C03067

Plugged through: TBG

INTOILED
6-21-06
2006061829

District: 04

Signed


(TECHNICIAN)

RECEIVED

JUN 21 2006

KCC WICHITA

JUN 13 2006

L G STEPHENSON & CO INC
 #670 7701 E KELLOGG #2 SCHARTZ 24-19-13W
 WICHITA, KS 67207 C N/2 N/2 NW
 CONTR REO TIGER DRLG CO CITY BARTON

SEOL _____ FIELD KOOPMAN

K 1838 KB CM 6/29/81 CARD ISSUED 8/20/81 IF SWOW
 ARB OH 3430-3550

Δ	+	+
+	+	+
+	+	+
+	+	+

API 15-009-22,414

SMP	TOPS	DEPTH	DATUM
ANH		715	+1123
TOP		2731	- 893
HEEB		3034	-1196
BR LM		3143	-1305
LANS		3157	-1319
B KC		3399	-1561
ARB		3425	-1587
TD		3550	-1712
NO LOG			

B-5/8" 344/250sx, 4 1/2" 3430/175sx
 DST (1) 3148-3215/60-45-60-45, 780'
 GIP, REC 120'GOCM, SIP 365-234#,
 FP 70-70#
 DST (2) 3210-3234/60-45-60-45, 840'
 GIP, REC 60'GOCM, SIP 85-85#, FP
 72-70#
 DST (3) 3282-3320/30-30-30-30, REC
 30' OIL SPTD M, SIP 67-52#, FP
 67-52#
 DST (4) 3377-3428/30-30-30-30, REC
 10' O STAINED M, SIP 1300-450#,
 FP 210-210#
 MICT - CO, (ARB OH) 3430-3550, NAT,
 INJECTION RATE SATISFACTORY, SWOW

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS