

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19034-00-00
Spot: NWSW Sec/Twnshp/Rge: 6-20S-11W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: ERNSTING Well #: 2
County: BARTON Total Vertical Depth: 3345 feet

Operator License No.: 32846
Op Name: PREMIER OIL & EXPLORATION INC
Address: 1100 AIRPORT RD
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3296	0	w/unknown sxs cmt
SURF	8.625	253	0	w/unknown sxs cmt

108.71

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/12/2006 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
1000' of tubing in the hole - approximately 33 joints down holes in casing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/13/2006 10:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

06/12/2006 - Witnessed by Pat Staab and Marvin Mills.
RIH with tubing to 2006'. Rigged to tubing and pumped 100 sxs 60/40 pozmix.
Pulled tubing to 1400'. Rigged to tubing and pumped 100 sxs 60/40 pozmix.
Max. P.S.I. 1400# to 1600#.
Pulled tubing to 500' and pumped 130 sxs 60/40 pozmix - cement did not circulate - out of casing at 5:00pm.
Rigged to 8 5/8" casing and pumped 5 sxs with 100# P.I.P. Blew hole in top of head - backside full of cement.
06/13/2006 - Witnessed by Marvin Mills
RIH with cement to 1190' and topped with 80 sxs cement. Hole full.

Remarks: COPELAND ACID SERVICES-TICKET #C030472.

Plugged through: TBG

INVOICED
DATE 6-21-06
BY 2006061830

District: 04

Signed _____

(TECHNICIAN)

JUN 15 2006

RECEIVED
JUN 21 2006
KCC WICHITA

PST