

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03438-00-00
Spot: NENENW Sec/Twnshp/Rge: 25-11S-17W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: CALAHAN B Well #: 6
County: ELLIS Total Vertical Depth: 3450 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3405	0	150 SX
SURF	8.625	1070	0	300 SX

\$ 112.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/16/2006 9:30 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered out 280 sxs 60/40 pozmix - 10% gel - 12 sxs gel - 400# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/16/2006 11:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1070' and 460'.
TIH with tubing to 2600' - mixed and pumped 12 sxs gel followed with 50 sxs cement with 300# hulls.
Pulled up to 1600' and circulated cement up 5 1/2".
POOH. Swaged onto 5 1/2" and 80 sxs circulating cement up 8 5/8" - shut in.
Topped with 20 sxs cement. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3405	3417		ARB
3186	3274		LKC
2876	3076		TOPEKA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

INVOICED

DATE 6-21-06
2006061832

District: 04

Signed

(TECHNICIAN)

RECEIVED

JUN 21 2006

KCC WICHITA

Form CP-2/3

JUN 19 2006