

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20221-00-00
Spot: SENESW Sec/Twnshp/Rge: 17-11S-16W
1650 feet from S Section Line, 2310 feet from W Section Line
Lease Name: CHESNEY Well #: 2
County: ELLIS Total Vertical Depth: 3325 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3285		
PROD	5.5	3322	0	150 SX
SURF	8.625	967	0	450 SX

\$ 108.06

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2006 9:30 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered out 260 sxs 60/40 pozmix - 10% gel - 12 sxs gel - 400# hulls. CIBP at 3285'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2006 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 420' - 970' - 1550'.
TIH with tubing to 2600' - mixed and pumped 12 sxs gel, followed with 50 sxs cement with 300# hulls.
Pulled up to 1550' - circulated cement with 140 sxs.
POOH. Swaged onto 5 1/2" - tied on and circulated cement up 8 5/8" - shut in.
Topped with 65 sxs cement. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3319	3322		
3250	3257		
3041	3046		
3005	3008		
2937	2939		
289	297		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

INVOICED
DATE 6-21-06
NO. 2006061832

District: 04

Signed Jay Pfeifer (TECHNICIAN)

RECEIVED
JUN 21 2006
KCC WICHITA
JUN 15 2006

VINCENT E. HIEBSCH

#2 CHESNEY

17 11 16W
APP SE NE SW

Contr. MURFIN DRLG

Cty. ELLIS

Geol. WAYNE WALCHER

Pool LIEB

E. 1772 KB Cm. 3/10/68 Cp. 4/25/68 IP P 69 BOPD/ARB

3322-25

API 15-051-20,221

SMP Tops	Depth	Datum	Csg. 8" 967/500 SK, 5" 3322/17 SK
			DST 3022-50/1', 120' MW W/SC O
ANH?	959	+ 813	BHP 787-725#/30", FP 73-89#
TOP	2690	- 918	DST 3049-77/1', 300' GP, 300'
HEFB	2923	-1151	G&OCMW, 420' SOCW, BHP 715-
TOR	2947	-1175	704#/30", FP 84-423#
LANS	2967	-1195	DST 3128-85/1', 75' MD, BHP 860-
BKC	3210	-1438	413#/30", FP 63-100#
CONG	3255	-1483	DST 3300-25/1', 420' GO, 900' SM
SIMP	3289	-1517	CO, BHP 1078 1078#/30", FP
ARB	3320	-1548	52-518#
RTD	3325	-1553	CO, FU 1000' OIL, BLD 3 BOPH,
			1000' OB, FU 2700' OIL/12 HRS,
			POP.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS