

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24896-00-00
Spot: W2SEW Sec/Twnshp/Rge: 4-13S-16W
3300 feet from S Section Line, 3630 feet from E Section Line
Lease Name: PFEIFER Well #: 1
County: ELLIS Total Vertical Depth: 3505 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3504	0	w/125 sxs cmt
SURF	8.625	216	0	w/140 sxs cmt

\$ 113.91

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2006 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE ACHTERBERG Company: NIXON, RP OPERATIONS, INC. Phone: (785) 628-3834

Proposed Plugging Method: Ordered 210 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2006 10:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perf at 1140' w/325 sxs cement (to circulate).
Tied to 4 1/2" casing and squeezed 200 sxs cement with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.
Tied to 8 5/8" x 4 1/2" annulus and pressured to 600 P.S.I. - took no cement.
Total of 200 sxs 60/40 pozmix - 10% gel - 500# hulls.

Perfs:

Remarks: ALLIED CEMENTING COMPANY, HERTEL TANK-WATER.

Plugged through: CSG

INVOICED
6-19-06
2006061812

District: 04

HD

Signed

Roger Z. Moses
(TECHNICIAN)

RECEIVED

JUN 16 2006

KCC WICHITA

Form CP-2/3

JUN 14 2006

PKT

replacement card

R P NIXON OPERATIONS
HAYS KS 67601

4-13S-16W
C W/2 SE NW

1 PFEIFER

site: 1-1/2 N & 5-1/2 E OF CATHERINE KS

city: ELLIS

API 15-051-24896

contr: SHIELDS DRILLING # 1

field: EMMERAM

opdr: DAN A NIXON

tr
date 05/23/95

spdr
date 06/26/95

drig
comp 07/02/95

card
issued 10/23/95

last
revised 09/09/96

ELV: 1994 KB, 1989 GL LOG

tops.....	depth/datum
ANH.....	1130 + 864
B/ANH.....	1166 + 828
TOP.....	2925 - 931
HEEB.....	3173 - 1179
TOR.....	3193 - 1199
LANS.....	3222 - 1228
PBTD.....	3440 - 1446
BKC.....	3455 - 1461
ARB DOL.....	3473 - 1479
LTD.....	3504 - 1510
RTD.....	3505 - 1511

IP status:

OIL, P 89 BO & 13 BWPD, LKC 3249-3386, 08/15/95
 CORR & INFO REL: 9/9/96 - CORR TOPS & ADDED PFS
 CSG: 8-5/8" 216 / 140 SX (ALT 2), 4-1/2" 3504 / 125 SX
 NO CORES OR DSTS
 TRGT ZN: LKC, ARB, PTD 3500 (ARB), MICT - CO, PF
 (ARB) 3482-3486, 3432-3434, W / 4 SPF, AC 500 GAL, SWB
 5 BFPH (3-4% OIL), SET CIBP AT 3440, PF (LKC) 3384-
 3386, 3303-3305, 3266-3268, 3249-3251, W / 2 SPF, AC 4000
 GAL & 2000 GAL SW SW FLUSH, GSO, SET 2-3/8" TBG
 AT 3425, POP, IPP 89 BO & 13 BWPD, 8/15/95; UPDATE:
 STAB AT P 28 BOPD & WTR, 10/15/95

COPYRIGHT 1996
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS