

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19036-00-00  
Spot: E2SESW Sec/Twnshp/Rge: 6-20S-11W  
660 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: ERNSTING Well #: 1  
County: BARTON Total Vertical Depth: 3335 feet

Operator License No.: 32846  
Op Name: PREMIER OIL & EXPLORATION INC  
Address: 1100 AIRPORT RD  
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	1000		
PROD	5.5	3332	0	w/unknown sxs cmt
SURF	8.625	234	0	w/unknown sxs cmt

#108.39

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/13/2006 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/13/2006 6:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

RIH with tubing to 2000'.  
Rigged and pumped 50 sxs cement with 100# hulls.  
Pulled to 1400' with 50 sxs cement and 100# hulls.  
Pulled to 900' with 75 sxs cement and 50# hulls - squeezed to 500#.  
Tied on backside and pumped 75 sxs cement.  
Squeezed to 200#. Hole full of cement.

Perfs:

Remarks: COPELAND ACID SERVICE-TICKET #C030474.

Plugged through: TBG

INVOICED  
DATE 6-19-06  
2006061813

District: 04

Signed

*Marvin Mills*

(TECHNICIAN)

100

RECEIVED

JUN 16 2006

KCC WICHITA

Form CP-2/3

JUN 14 2006

PET